

Source Test Report

Great Lakes Water Authority Wastewater Resource Recovery Facility 9300 W. Jefferson Avenue Detroit, Michigan 48209

Sources Tested: Multiple Heart Incinerator- Unit 14 (EUINC14) Test Date: July 12, 2023

Project No. AST-2023-1997

Prepared By Alliance Technical Group, LLC Boston Office 1020 Turnpike Street Canton, MA 02021



Regulatory Information

Permit No.	ROP No. MI-ROP-B2103-2014d
Regulatory Citations	40 CRF 60, Subpart MMMM, Rule 972
Regulatory Agency	Michigan Department of Environment, Great Lakes, and Energy (EGLE)

Source Information

Source Name Multiple Heart Incinerator- Unit 14 Source ID EUINC14 Target Parameter(s) NO_x

Contact Information

Test Location Great Lakes Water Authority Water Resource Recovery Facility 9300 W. Jefferson Avenue Detroit, MI 48209

Facility Contact Melvin Dacres melvin.dacres@glwater.org (313)297-0363 Test Company Alliance Technical Group, LLC Boston Office 1020 Turnpike Street Canton, MA 02021

Project Manager Michael Kelley michael.kelley@alliancetg.com (781) 799-0710

Field Team Leader Brendan Kelley brendan.kelley@alliancetg.com (781) 770-8618

QA/QC Manager Kathleen Shonk katie.shonk@alliancetg.com (812) 452-4785

Report Coordinator Esther Durex esther.durex@alliancetg.com (781) 828-5200



Alliance Technical Group, LLC (Alliance) has completed the source testing as described in this report. Results apply only to the source(s) tested and operating condition(s) for the specific test date(s) and time(s) identified within this report. All results are intended to be considered in their entirety, and Alliance is not responsible for use of less than the complete test report without written consent. This report shall not be reproduced in full or in part without written approval from the customer.

To the best of my knowledge and abilities, all information, facts, and test data are correct. Data presented in this report has been checked for completeness and is accurate, error-free, and legible. Onsite testing was conducted in accordance with approved internal Standard Operating Procedures. Any deviations or problems are detailed in the relevant sections in the test report.

This report is only considered valid once an authorized representative of Alliance has signed in the space provided below; any other version is considered draft. This document was prepared in portable document format (.pdf) and contains pages as identified in the bottom footer of this document.

Mike Kelley Project Manager Alliance Technical Group, LLC 08/03/23 Date



Source Test Report Table of Contents

TABLE OF CONTENTS

1.0	Introduction
1.1	Facility Description1-1
1.2	Emission Unit and Control Unit Descriptions 1-1
1.3	Project Team
1.4	Test Protocol & Notification
1.5	Test Program Notes
2.0	Summary of Results
3.0	Testing Methodology
3.1	U.S. EPA Reference Test Method 3/3A – Oxygen/Carbon Dioxide
3.2	U.S. EPA Reference Test Method 7E – Nitrogen Oxides
3.3	Quality Assurance/Quality Control – U.S. EPA Reference Test Methods 3A and 7E 3-1

LIST OF TABLES

Table 1-1:	Project Team 1-	1
Table 2-1:	Summary of Results MHI 142-	1
Table 3-1:	Source Testing Methodology	1

APPENDICES

Appendix A	Sample Calculations
Appendix B	Field Data
Appendix C	Laboratory Report
Appendix D	Quality Assurance/Quality Control Data
Appendix E	Process Operating/Control System Data
Appendix F	CSV Data

A Street & Parabativat

"A WA APPENDENT AT MERINA MARK MARK MARK I SE SE EN EN ALAR EN PRANK AL EN EL MELLEN PER PER EN EN PARTA Meliant MERINE AL EL Par ENVERNING EN ENVERTE UNE SPREN HELSE MARK MINNEN EN EL EN EL EN EN EL EN ENVER 1931 PÉRE MARK EN AND AND ANNEL EN ENVERTE ENVERTE MARK AL MELLEN VILLE AND EL EN EL EN EL EN EL EN EL EN ENVER AND PÉRE MARK EN AND AND AND ANNEL EN ENVERTE ENVERTE MARK AN ANTERE AL MELLEN PER PER ENTER AND EN EL EN ENVER

> na on agenta agenta piero de agenta a de pierdemo Astala de la una como a de como como a de la s

Introduction

ingente for selation fritte anna 2 f. marcan confinations (1980)

7.5. Der Some por Göner wich delingebilder ist das värige Beweisen SP-and-PU-PU-PU-PU-PU-PU-PU-PU-PU-PU-PU-PUer some ger Aparten af konstite C. A. M. F. PE-NDA 12. The Bong arte of the Fernance to accident (1999). C. Francesan sectors are examine the alcound to be fungementation.

configure end style (concept) for the endployed of the sector (concept) and the sector (concept) and the sector (concept) is a sector (concept) of the sector (concept) is a sector (concept) is a

(a) a proposition reported systems and shareholder. So a first independent of the end of the second state of the end of the second state of the

President de la complicación de Stankas Levense, en estre égnifica de la completa da completa da la completa d A 2010 forma interval da la frecidad de la conselénse a complete especielar, con el consta a forma da conselecc A 101 marco da la conselección

> tut — An preticiona. No e avel to are diseare proportium dando di arte con o un nene

AND LODGED AND AND A



1.0 Introduction

Alliance Technical Group, LLC (Alliance) was retained by Great Lakes Water Authority (GLWA) to conduct compliance testing at the Water Resource Recovery Facility (WRRF) in Detroit, Michigan (MI). Portions of the facility are subject to 40 Code of Federal Regulations (CFR) Part 60 Subpart MMMM. The facility operates under the Renewable Operating Permit. (ROP) No. MI-ROP-B2103-2014d. Testing was conducted to determine the emission rate of Nitrogen Oxides (NOx), at the exhaust of Multiple Hearth Incinerator (MHI) 14.

1.1 Facility Description

GLWA operates an incineration complex. The incineration complex contains eight sewage sludge incinerators subject to the 40 CFR Part 60, Subpart MMMM emissions guidelines though Rule 972. Sludge is dewatered with belt filter presses and conveyed to the multiple hearth furnaces with belt conveyors. The sludge conveyors are equipped with weigh scales for continuous monitoring of the amount of sludge being incinerated. The dewatered sludge is introduced at the top hearth and rabbled down through successive hearths in a spiral path. The moisture in the sludge is evaporated in the upper hearths as hot combustion gases traveling concurrently from the middle hearths where combustion takes place. The maximum feed rate is 3.12 dry tons per hour at 25% solids and 75% volatiles condition. It is a continuous feed process. Under normal operating conditions each incinerator runs between 2.0 and 2.5 dry tons per hour with temperature of the solids between 50 and 80 °F. The furnace is equipped with auxiliary natural gas burners at hearths 2, 4, 6, 8, 10, and 12. The firing rate of the burners is modulated by a central control system to sustain the desired hearth temperatures.

1.2 Emission Unit and Control Unit Descriptions

Each air pollution control system is comprised of a Double Zero Hearth afterburner section of Hearths 1 and 2, a quench section, and EnviroCare® Venturi-Pak (venturi throat sections and mist eliminator) scrubber system. The total pressure-drop across the wet scrubber ranges between 25 and 40 inches of water column (in. wc). The total scrubber water flow should be greater than 1416 gallons per minute (gpm). Exhaust gases pass through this MHI via an induced draft (ID) fan and exit the scrubber at 100- 150 °F.

There have not been any equipment modifications, failures, or any significant adjustments or maintenance since the last performance test. There have not been any emissions-related engineering evaluations conducted on the system since the last performance test.

1.3 Project Team

Personnel involved in this project are identified in the following table.

Table 1-1: Project Team

Alliance Personnel	Brendan Kelley		
Amance rersonner	Kenny Huang		


1.4 Test Protocol & Notification

Testing was conducted in accordance with the test protocol submitted to Michigan Department of Environment, Great Lakes, and Energy (EGLE) on June 1, 2023.

1.5 Test Program Notes

Testing was completed without any deviations.

STREET And Street Markholmer B. S. Street





2.0 Summary of Results

Alliance conducted compliance testing at the GLWA WRRF facility in Detroit, MI on July 12, 2023. Testing consisted of determining the emission rates of NO_x at the exhaust of MHI 14.

Table 2-1 provides a summary of the emission testing results with comparisons to the applicable permit limits. Any difference between the summary results listed in the following table and the detailed results contained in appendices is due to rounding for presentation.

Run Number	Run 1	Run 2	Run 3		
Date	7/12/23	7/12/23	7/12/23	A	
Start Time	9:16	10:41	12:11	Average	
Stop Time	10:16	11:41	13:11		
Oxygen Data					
Concentration, % dry	12.77	12.30	12.42	12.50	
Carbon Dioxide Data					
Concentration, % dry	6.74	7.20	7.13	7.02	
Nitrogen Oxides Data					
Concentration, ppmvd	95.73	109.11	120.95	108.60	
Concentration, ppmvd @ 7 % O2	163.59	176.35	198.35	179.43	
Permit Limit, ug ppmvd @ 7 % O2				220	
Percent of Limit, %				82	

Table 2-1: Summary of Results MHI 14

A 1743 114 (20) utgete al " (20) utgete al bodinar (20) utgete And Santa (20) utgete And Santa

Testing Methodology

u ha i valižite Naj o i stra Interne anti

2.1 In N. M. S. Parkitegia: And Marked (2). If the gravitation frightly gravitation (2014) is sampled to consider a consistence of the Construction (2) in a 2000 of the second of neural for the second of the consistence of the Construction (2) in a 1000 or 2010 county (2010) is constructed to compare and developments of an even (2). And the construction and a material cost matching of the construction and developments of an even (2). And the construction and a material cost matching of the cost of the construction of the construction of the cost of the cost of and a material cost matching of the cost of the construction of the construction of the cost of the cost of a second of the cost of the cost of the construction of the construction of the cost of the cost of resonants of the cost of the cost of the construction of the cost of

> 유가 - - - Sparkey, weaterweakly in a spin family - - - - Scaffeb - Adder dates it is traditate for a de Co 2005 - Coloret - E. C., Paerley - J. S

ian musikano terketu tekuu. 1933 Biston du mili Ajenari nin Kega ar terkin au an olimpu un olimpu uun. Berikisi berajini. Ar - arti terkipine af Serasi.

the second second second second second

Control and the state of the second state of the second state of the constant of the consect of the second state of the sec



3.0 Testing Methodology

The emission testing program was conducted in accordance with the test methods listed in Table 3-1. Method descriptions are provided below while quality assurance/quality control data is provided in Appendix C.

Table 3-1:	Source	Testing	Methodology
------------	--------	---------	-------------

Parameter	U.S. EPA Reference Test Methods	Notes/Remarks
Oxygen/Carbon Dioxide	3A	Instrumental Analysis
Nitrogen Oxides	7E Instrumental A	

3.1 U.S. EPA Reference Test Method 3/3A – Oxygen/Carbon Dioxide

The oxygen (O_2) and carbon dioxide (CO_2) testing was conducted in accordance with U.S. EPA Reference Test Method 3A. Data was collected online and reported in one-minute averages. The sampling system consisted of a stainless-steel probe, heated Teflon sample line(s), gas conditioning system and the identified gas analyzer. The gas conditioning system was a non-contact condenser used to remove moisture from the stack gas. The quality control measures are described in Section 3.3.

3.2 U.S. EPA Reference Test Method 7E – Nitrogen Oxides

The nitrogen oxides (NOx) testing was conducted in accordance with U.S. EPA Reference Test Method 7E. Data was collected online and reported in one-minute averages. The sampling system consisted of a stainless-steel probe, heated Teflon sample line(s), gas conditioning system and the identified gas analyzer. The gas conditioning system was a non-contact condenser used to remove moisture from the stack gas. The quality control measures are described in Section 3.3.

3.3 Quality Assurance/Quality Control – U.S. EPA Reference Test Methods 3A and 7E

EPA Protocol 1 Calibration Gases

Cylinder calibration gases used met EPA Protocol 1 (+/- 2%) standards. Copies of all calibration gas certificates can be found in the Quality Assurance/Quality Control Appendix.

Direct Calibration & Calibration Error Test

Low Level gas was introduced directly to the analyzer. After adjusting the analyzer to the Low-Level gas concentration and once the analyzer reading was stable, the analyzer value was recorded. This process was repeated for the High-Level gas. For the Calibration Error Test, Low, Mid, and High Level calibration gases were sequentially introduced directly to the analyzer. All values were within 2.0 percent of the Calibration Span or 0.5 ppmv/% absolute difference.

System Bias and Response Time

High or Mid Level gas (whichever was closer to the stack gas concentration) was introduced at the probe and the time required for the analyzer reading to reach 95 percent or 0.5 ppmv/% (whichever was less restrictive) of the gas concentration was recorded. The analyzer reading was observed until it reached a stable value, and this value was recorded. Next, Low Level gas was introduced at the probe and the time required for the analyzer reading to decrease to a value within 5.0 percent or 0.5 ppmv/% (whichever was less restrictive) was recorded. If the Low-



Level gas was zero gas, the response was 0.5 ppmv/% or 5.0 percent of the upscale gas concentration (whichever was less restrictive). The analyzer reading was observed until it reached a stable value and this value was recorded. The measurement system response time and initial system bias were determined from these data. The System Bias was within 5.0 percent of the Calibration Span or 0.5 ppmv/% absolute difference.

Post Test System Bias Checks

High or Mid Level gas (whichever was closer to the stack gas concentration) was introduced at the probe. After the analyzer response was stable, the value was recorded. Next, Low Level gas was introduced at the probe, and the analyzer value recorded once it reached a stable response. The System Bias was within 5.0 percent of the Calibration Span or 0.5 ppmv/% absolute difference or the data was invalidated and the Calibration Error Test and System Bias were repeated.

Post Test Drift Checks

Drift between pre- and post-run System Bias was within 3 percent of the Calibration Span or 0.5 ppmv/% absolute difference. If the drift exceeded 3 percent or 0.5 ppmv/%, the Calibration Error Test and System Bias were repeated.

Stratification Check

To determine the number of sampling points, a gas stratification check was conducted prior to initiating testing. The pollutant concentrations were measured at three points (16.7, 50.0 and 83.3 percent of the measurement line). Each traverse point was sampled for a minimum of twice the system response time.

If the pollutant concentration at each traverse point did not differ more than 5 percent or 0.5 ppmv/0.3% (whichever was less restrictive) of the average pollutant concentration, then single point sampling was conducted during the test runs. If the pollutant concentration did not meet these specifications but differed less than 10 percent or 1.0 ppmv/0.5% from the average concentration, then three (3) point sampling was conducted (stacks less than 7.8 feet in diameter - 16.7, 50.0 and 83.3 percent of the measurement line; stacks greater than 7.8 feet in diameter -0.4, 1.0, and 2.0 meters from the stack wall). If the pollutant concentration differed by more than 10 percent or 1.0 ppmv/0.5% from the average concentration, then sampling was conducted at a minimum of twelve (12) traverse points. Copies of stratification check data can be found in the Quality Assurance/Quality Control Appendix.

NO_x Converter Check

An $NO_2 - NO$ converter check was performed on the analyzer prior to initiating testing and at the completion of testing. An approximately 51 ppm nitrogen dioxide cylinder gas was introduced directly to the NOx analyzer and the instrument response was recorded in an electronic data sheet. The instrument response was within +/- 10 percent of the cylinder concentration.

Data Collection

A Data Acquisition System with battery backup was used to record the instrument response in one (1) minute averages. The data was continuously stored as a *.CSV file in Excel format on the hard drive of a computer. At the completion of testing, the data was also saved to the Alliance server. All data was reviewed by the Field Team Leader before leaving the facility. Once allying a compared by the Project Manager. relinquished to the report coordinator and then a final review was performed by the Project Manager. RECEIVED



Appendix A



 Location:
 Great Lakes Water Authority - Detroit, MI

 Source:
 Incinerator 14 (EUINC14)

 Project No.:
 AST-2023-1997

 Run No. /Method
 Run 1 / Method 3A

 O_2 - Outlet Concentration (C $_{O_2}\!),\,\%$ dry

$$C_{O_2} = (C_{obs} - C_0) x \left(\frac{C_{MA}}{(C_M - C_0)} \right)$$

where,

 $\begin{array}{c|c} C_{obs} & 12.4 & = average analyzer value during test, \% dry \\ \hline C_o & 0.0 & = average of pretest & posttest zero responses, \% dry \\ \hline C_{MA} & 10.0 & = actual concentration of calibration gas, \% dry \\ \hline C_M & 9.7 & = average of pretest & posttest calibration responses, \% dry \\ \hline C_{O_2} & 12.8 & = O_2 \text{ Concentration, \% dry} \end{array}$



Location:	Great Lakes Water Authority - Detroit, MI
Source:	Incinerator 14 (EUINC14)
Project No.:	AST-2023-1997
Run No. /Method	Run 1 / Method 3A

CO₂ - Outlet Concentration (C_{CO₂}), % dry

$$C_{CO_2} = \left(C_{obs} - C_0 \right) x \quad \left(\frac{C_{MA}}{(C_M - C_0)} \right)$$

where,

Cobs	6.5	= average analyzer value during test, % dry
C.	0.2	= average of pretest & posttest zero responses, % dry
C _{MA}	10,0	= actual concentration of calibration gas, % dry
C _M	9.6	= average of pretest & posttest calibration responses, % dry
C _{CO2}	6.7	= CO ₂ Concentration, % dry



Location: Great Lakes Water Authority - Detroit, MI Source: Incinerator 14 (EUINC14) Project No.: AST-2023-1997 Run No. /Method Run 1 / Method 7E

NOx - Outlet Concentration (C_{NOx}), ppmvd

$$C_{NOx} = (C_{obs} - C_0) x \left(\frac{C_{MA}}{(C_M - C_0)} \right)$$

where,

C_{obs}	96.7	= average analyzer value during test, ppmvd
Co	1.9	= average of pretest & posttest zero responses, ppmvd
C _{MA}	239.1	= actual concentration of calibration gas, ppmvd
C _M	238.7	= average of pretest & posttest calibration responses, ppmvd
C _{NOx}	95.7	= NOx Concentration, ppmvd

NOx - Outlet Concentration (C_{NOxc7}), ppmvd @ 7% O₂

$$C_{NOxc7} = C_{NOx} x$$

where,

$$\begin{array}{c|c} C_{NOx} & 95.7 & = NOx - Outlet Concentration, ppmvd \\ \hline C_{O_2} & 12.8 & = oxygen \ concentration, \% \\ \hline C_{NOxc7} & 163.6 & = ppmvd \ @7\% \ O_2 \end{array}$$

 $\left(\begin{array}{c} 20.9 - 7\\ \hline 20.9 - O_2 \end{array}\right)$

Appendix B



Location Great Lakes Water Authority - Detroit, MI

Source Incinerator 14 (EUINC14)

Project No. AST-2023-1997

Run Number	Run 1	Run 2	Run 3	Average			
Date		7/12/23	7/12/23	7/12/23			
Start Time		9:16	10:41	12:11			
Stop Time		10:16	11:41	13:11			
Calculated Data - Outlet							
O2 Concentration, % dry	C _{O2}	12.77	12.30	12.42	12.50		
CO ₂ Concentration, % dry	C _{CO2}	6.74	7.20	7.13	7.02		
NOx Concentration, ppmvd	C _{NOx}	95.73	109.11	120.95	108.60		
NOx Concentration, ppmvd @ 7 % O2	C _{NOxc7}	163.59	176.35	198.35	179.43		




Method 1 Data


Location Great Lakes Water Authority - Detroit, MI

Source Incinerator 14 (EUINC14)
Project No. AST-2023-1997

Project No. AST-2023-1997 Date: 07/11/23

Stack Parameters





							CIRCUI	AR DUCT								
 LOCATION OF TRAVERSE POINTS Number of traverse points on a diameter													averse Point	% of Diameter	Distance from inside wall	Distance from outside of
	2	3	4	5	6	7	8	9	10	11	12					port
1	14.6	16.7	6.7		4.4		3.2		2.6		2.1		1	16.7	9.02	12.02
2	85.4	50.0	25.0		14.6		10.5		8.2	-	6.7		2	50.0	27.00	30.00
3	-	83.3	75.0		29.6		19.4		14.6	-	11.8		3	83.3	44.98	47.98
4	-		93.3	-	70.4		32.3	-	22.6	-	17.7		4			
5	-	-		-	85.4		67.7		34.2	-	25.0		5			
6			-	-	95.6		80.6	-	65.8		35.6		6			
7	-		-				89.5	-	77.4	-	64.4		7			
8	-		-				96.8		85.4		75.0		8			
9	-	-	-						91.8		82.3		9			
10	-		-	-				-	97.4	-	88.2		10			
11	-	-	-	-						-	93.3		11			
12	-	-	-	-				-			97.9		12			

*Percent of stack diameter from inside wall to traverse point.

