



Compliance Emissions Test Report

**Lansing Board of Water and Light
REO Town Facility
Auxiliary Boiler Stack
Lansing, Michigan
February 12, 2019**

RECEIVED
MAR 13 2019
AIR QUALITY DIVISION

**Report Submittal Date
March 7, 2019**

© Copyright 2019
All rights reserved in
Mostardi Platt

Project No. M190706A

TABLE OF CONTENTS

1.0 EXECUTIVE SUMMARY	1
2.0 TEST METHODOLOGY	2
Method 1 Traverse Point Determination	2
Gaseous Stratification Test	2
Method 2 Volumetric Flowrate Determination	2
Method 3A Oxygen (O ₂)/Carbon Dioxide (CO ₂) Determination	2
Method 5 Filterable Particulate Matter (FPM) Determination	3
Method 202 Condensable Particulate Matter (CPM) Determination	3
Method 10 Carbon Monoxide (CO) Determination	3
3.0 TEST RESULT SUMMARIES	4
4.0 CERTIFICATION	6
APPENDICES	
Appendix A - Plant Operating Data	8
Appendix B - Test Section Diagrams	20
Appendix C - Sample Train Diagrams	24
Appendix D - Calculation Nomenclature and Formulas	29
Appendix E - Laboratory Sample Analysis	40
Appendix F - Reference Method Test Data (Computerized Sheets)	44
Appendix G - Field Data Sheets	59
Appendix H - Calibration Data	72
Appendix I - Gas Cylinder Certifications	91

1.0 EXECUTIVE SUMMARY

MOSTARDI PLATT conducted a compliance emissions test program for Lansing Board of Water and Light on February 12, 2019 at the REO Town Facility in Lansing, Michigan on the Auxiliary Boiler Stack. This report summarizes the results of the test program and test methods used.

The test location, test date, and test parameters are summarized below.

TEST INFORMATION		
Test Location	Test Date	Test Parameters
Auxiliary Boiler Stack	February 12, 2019	Filterable Particulate Matter (FPM), Condensable Particulate Matter (CPM), Total Particulate Matter (TPM), and Carbon Monoxide (CO)

The purpose of the test program was to demonstrate the above test parameter emissions during normal operating conditions to satisfy the regulatory permit limits. Selected results of the test program are summarized below. A complete summary of emission test results follows the narrative portion of this report.

TEST RESULTS			
Test Location	Test Parameter	Emission Limits	Emission Rate
Auxiliary Boiler Stack	FPM	0.5 lb/hr	0.096 lb/hr
	TPM (PM _{2.5} , PM ₁₀)	1.8 lb/hr	0.341 lb/hr
	CO	0.04 lb/mmBtu	0.037 lb/mmBtu

All of the filterable and condensable particulate matter were considered to be PM_{2.5} and PM₁₀ in the TPM evaluation. Operating data as provided by Lansing Board of Water and Light are included in Appendix A. FPM/TPM Run 1 failed the post leak check. A fourth run was performed, and the FPM/TPM results are based on Runs 2 through 4.

The identifications of individuals associated with the test program are summarized below.

TEST PERSONNEL INFORMATION		
Location	Address	Contact
Test Coordinator	Lansing Board of Water and Light 1232 Haco Drive P.O. Box 13007 Lansing, Michigan 48912	Mr. Nathan Hude Environmental Regulatory Compliance (517) 490-3069 (cell phone) nathan.hude@lbwl.com
Test Facility	Lansing Board of Water and Light REO Town Facility 1201 S. Washington Ave. Lansing, Michigan 48917	
Testing Company Representative	Mostardi Platt 888 Industrial Drive Elmhurst, Illinois 60126	Mr. Mark E. Peterson Project Manager (630) 993-2100 (phone) mpeterson@mp-mail.com

The test crew consisted of Messrs. J. Adams, J. Kukla, K. Krofel, and M. Peterson of Mostardi Platt.

2.0 TEST METHODOLOGY

Emissions testing was conducted following the methods specified in 40CFR60, Appendix A, and 40CFR51, Appendix M. A schematic of the test section diagram is found in Appendix B and schematics of the sampling trains used are included in Appendix C. Calculation nomenclature and sample calculations are included in Appendix D. Laboratory analysis data are found in Appendix E. Copies of analyzer print-outs for each test run are included in Appendix F and field data sheets are found in Appendix G.

The following methodologies were used during the test program:

Method 1 Traverse Point Determination

Test measurement points were selected in accordance with Method 1. The characteristics of the measurement location are summarized below.

TEST POINT INFORMATION						
Location	Stack Diameter	Stack Area	Upstream Diameters	Downstream Diameters	Test Parameter	Number of Sampling Points
Auxiliary Boiler Stack	4' 9"	17.72 sq. ft.	~45 feet	~53 feet	FPM, TPM	24

Gaseous Stratification Test

A twelve-point stratification test was performed during Run 1 of the test program. Based on the stratification test results, three test point used for Runs 2 and 3.

Method 2 Volumetric Flowrate Determination

Gas velocity was measured following Method 2, for purposes of calculating stack gas volumetric flow rate and FPM/TPM emissions on a lb/hr basis. An S-type pitot tube, differential pressure gauge, thermocouple and temperature readout were used to determine gas velocity at each sample point. All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H.

Method 3A Oxygen (O₂)/Carbon Dioxide (CO₂) Determination

Stack gas molecular weight was determined in accordance with Method 3A. A Servomex analyzer was used to determine stack gas oxygen and carbon dioxide content and, by difference, nitrogen content. All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H and copies of the gas cylinder certifications are found in Appendix I.

Method 5 Filterable Particulate Matter (FPM) Determination

Stack gas filterable particulate concentrations and emission rates were determined in accordance with Method 5. An Environmental Supply Company, Inc. sampling train was used to sample stack gas at an isokinetic rate, as specified in the Method. Particulate matter in the sample probe was recovered using an acetone wash. The probe wash and filter catch were analyzed by Mostardi Platt personnel. Laboratory analysis data are found in Appendix E. Calibration data are presented in Appendix H.

Method 202 Condensable Particulate Matter (CPM) Determination

Stack gas CPM concentrations and emission rates were determined in accordance with the Method 202, 40CFR51, Appendix M, in conjunction with Method 5 filterable particulate sampling. Condensable particulate matter was collected in the impinger portion of the Method 202 sampling train.

The condensable particulate matter (CPM) was collected in impingers after filterable particulate material was collected using Method 5. The organic and aqueous fractions were then taken to dryness and weighed. The total of all fractions represents the CPM. Compared to the December 17, 1991 promulgated Method 202, this Method includes the addition of a condenser, followed by a water dropout impinger immediately after the final heated filter. One modified Greenburg Smith impinger and an ambient temperature filter follow the water dropout impinger. A schematic of the sampling train configured with these updates is found in the Appendix.

CPM was collected in the water dropout, modified Greenburg Smith impinger and ambient filter portion of the sampling train as described in this Method. The impinger contents were purged with nitrogen (N₂) immediately after sample collection to remove dissolved sulfur dioxide (SO₂) gases from the impingers. The impinger solution was then extracted with DI water, acetone, and hexane. The organic and aqueous fractions were dried and the residues weighed. The total of the aqueous, organic, and ambient filter fractions represents the CPM. Laboratory analysis data are found in Appendix E. All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H.

Method 10 Carbon Monoxide (CO) Determination

Stack gas carbon monoxide concentrations and emission rates were determined in accordance with Method 10. A TECO 48i carbon monoxide analyzer was used to determine carbon monoxide concentrations, in the manner specified in the Method.

Stack gas was delivered to the analyzer via a Teflon® sampling line, heated to a minimum temperature of 250°F. Excess moisture in the stack gas was removed using a refrigerated condenser. The entire system was calibrated in accordance with the Method, using certified calibration gases introduced at the probe, before and after each test run.

A list of calibration gases used and the results of all calibration and other required quality assurance checks can be found in Appendix H. Copies of calibration gas certifications can be found in Appendix I.

3.0 TEST RESULT SUMMARIES

Client: Lansing Board of Water and Light
 Facility: REO Town Facility
 Test Location: Auxiliary Boiler Stack
 Test Method: 5/202

	Source Condition	Full Load	Full Load	Full Load	Full Load	
	Date	2/12/19	2/12/19	2/12/19	2/12/19	
	Start Time	10:00	13:00	15:25	18:34	
	End Time	12:17	15:05	17:49	20:38	Runs 2, 3, and 4
		Run 1	Run 2	Run 3	Run 4	Average
Stack Conditions						
Average Gas Temperature, °F		291.4	291.8	291.4	290.5	291.2
Flue Gas Moisture, percent by volume		14.8%	15.9%	15.8%	14.5%	15.4%
Average Flue Pressure, in. Hg		28.67	28.67	28.67	28.67	28.67
Gas Sample Volume, dscf		90.790	85.223	83.830	83.453	84.169
Average Gas Velocity, ft/sec		63.714	63.425	64.035	63.803	63.754
Gas Volumetric Flow Rate, acfm		67,743	67,436	68,084	67,837	67,786
Gas Volumetric Flow Rate, dscfm		38,888	38,173	38,621	39,118	38,637
Gas Volumetric Flow Rate, scfm		45,620	45,388	45,847	45,739	45,658
Average %CO ₂ by volume, dry basis		9.8	10.0	10.0	9.9	10.0
Average %O ₂ by volume, dry basis		4.0	3.5	3.4	3.7	3.5
Isokinetic Variance		109.8	105.0	102.1	100.3	102.5
Standard Fuel Factor Fd, dscf/mmBtu		8,710.0	8,710.0	8,710.0	8,710.0	8,710.0
Filterable Particulate Matter (Method 5)						
grams collected		0.00591	0.00156	0.00116	0.00200	0.00157
grains/acf		0.0006	0.0002	0.0001	0.0002	0.0002
grains/dscf		0.0010	0.0003	0.0002	0.0004	0.0003
lb/hr		0.335	0.092	0.071	0.124	0.096
lb/mmBtu (Standard Fd Factor)		0.0015	0.0004	0.0003	0.0006	0.0004
Condensable Particulate Matter (Method 202)						
grams collected		0.00494	0.00395	0.00362	0.00450	0.00402
grains/acf		0.0005	0.0004	0.0004	0.0005	0.0004
grains/dscf		0.0008	0.0007	0.0007	0.0008	0.0007
lb/hr		0.280	0.234	0.221	0.280	0.245
lb/mmBtu (Standard Fd Factor)		0.0013	0.0011	0.0010	0.0013	0.0011
Total Particulate Matter (5/202)						
grams collected		0.01085	0.00551	0.00478	0.00650	0.00560
grains/acf		0.0011	0.0006	0.0005	0.0007	0.0006
grains/dscf		0.0018	0.0010	0.0009	0.0012	0.0010
lb/hr		0.615	0.326	0.292	0.404	0.341
lb/mmBtu (Standard Fd Factor)		0.0028	0.0015	0.0013	0.0019	0.0016

Lansing Board of Water and Light
REO Town Facility
Auxiliary Boiler Stack
Gaseous Summary

Test No.	Date	Start Time	End Time	Fd Factor, dscf/MMBtu	CO ppmvd	CO ₂ % (dry)	O ₂ % (dry)	O2 based CO lb/MMBtu
1	02/12/19	10:00	11:04	8,710.0	44.1	9.9	3.5	0.034
2	02/12/19	11:30	12:32	8,710.0	50.3	10.0	3.7	0.039
3	02/12/19	13:20	14:19	8,710.0	49.6	10.0	3.7	0.038
Average				8,710.0	48.0	10.0	3.6	0.037

4.0 CERTIFICATION

MOSTARDI PLATT is pleased to have been of service to Lansing Board of Water and Light If you have any questions regarding this test report, please do not hesitate to contact us at 630-993-2100.

CERTIFICATION

As project manager, I hereby certify that this test report represents a true and accurate summary of emissions test results and the methodologies employed to obtain those results, and the test program was performed in accordance with the methods specified in this test report.

MOSTARDI PLATT



Program Manager

Mark E. Peterson



Quality Assurance

Jeffrey M. Crivlare